



PROJECT ID: Henson Rockland Key

SCOPE: Electrical



## CLIENT'S INFORMATION:

CONTACT:

E-MAIL ADDRESS:

PHONE NUMBER:

Date:

ITEM #	DWG. #	DESCRIPTION	QUANTITY	UNIT	MATERIAL	LABOR	UNIT COST (Labor + Material)	TOTAL COST	TRADE COST
<b>DIVISION 26- ELECTRICAL</b>									
<b>E0 Site Plan</b>									
8		Wall Pack W/ PC EM (WP5) Manufacturer: Lithonia Part Number: OWL-EM-XX-MB	21	EA	\$300	\$150	\$450	\$9,450	
9		Wall Pack (Forward Forward Throw) W/ PC OC 50% DIM EM (WP4) Manufacturer: Lithonia Part Number: WDGE3 LED P4 70CRI RFT 50K	12	EA	\$300	\$150	\$450	\$5,400	
10		Wall Pack (Type 2) W/ PC OC 50% DIM EM (WP2) Manufacturer: Lithonia Part Number: WDGE3 LED P1 70CRI R2 50K	4	EA	\$300	\$150	\$450	\$1,800	
11		Wall Pack (Forward Forward Throw) W/ PC OC 50% DIM EM (WP3) Manufacturer: Lithonia Part Number: WDGE3 LED P3 70CRI RFT 50K	8	EA	\$300	\$150	\$450	\$3,600	
12		Type IV Canopy Fixture (SA) Manufacturer: Lithonia Part Number: KACM LED 60C 530 50K R4 MVOLT	6	EA	\$300	\$150	\$450	\$2,700	
13		Disconnect Switch	1	EA	\$200	\$100	\$300	\$300	
14		Proposed Transformer Building C	1	EA	\$4,500	\$500	\$5,000	\$5,000	
15		Proposed Transformer Building A & B	1	EA	\$4,500	\$500	\$5,000	\$5,000	
16		Conduit/Conductor Line	618	FT	\$3	\$2	\$5	\$3,090	
<b>E1 Electrical Plan</b>									
<b>Building A - Electrical Plan</b>									
17		Emergency Light Fixture	4	EA	\$400	\$200	\$600	\$2,400	
18		Quadraplex Receptacle	8	EA	\$150	\$100	\$250	\$2,000	
19		Leviton ODS10 Infrared Wall Switch W/ Manual On/Auto Off	4	EA	\$80	\$50	\$130	\$520	
20		Ceiling or Wall Mounted Self Contained Emergency Exit Sign W/ Directional Arrows	8	EA	\$250	\$100	\$350	\$2,800	
21		Duplex Receptacle Weather Proof	1	EA	\$150	\$100	\$250	\$250	
22		Warehouse Fixture W/ OC 50% DIM (B2) Manufacturer: Lithonia Part Number: UFIT L48 10000LM HEF MVOLT EZ1 40K 80CRI WH LAHOSZU	40	EA	\$300	\$150	\$450	\$18,000	
23		Wall Mounted Vanity Fixture (A) Manufacturer: Lithonia Part Number: FMVCCLS 24IN MVOLT 40K 90CRI BN M6	4	EA	\$300	\$150	\$450	\$1,800	
24		Three Way Switch	8	EA	\$80	\$50	\$130	\$1,040	
25		Motor Rated Switch	4	EA	\$80	\$50	\$130	\$520	
26		Allowances and Conduits	9000	SF	\$1	\$1	\$2	\$18,000	
<b>Building B - Electrical Plan</b>									
27		Leviton ODS10 Infrared Wall Switch W/ Manual On/Auto Off	4	EA	\$80	\$50	\$130	\$520	
28		Ceiling or Wall Mounted Self Contained Emergency Exit Sign W/ Directional Arrows	8	EA	\$250	\$100	\$350	\$2,800	
29		Wall Mounted Vanity Fixture (A) Manufacturer: Lithonia Part Number: FMVCCLS 24IN MVOLT 40K 90CRI BN M6	4	EA	\$300	\$150	\$450	\$1,800	
30		Warehouse Fixture W/ OC 50% DIM (B2) Manufacturer: Lithonia Part Number: UFIT L48 10000LM HEF MVOLT EZ1 40K 80CRI WH LAHOSZU	40	EA	\$300	\$150	\$450	\$18,000	
31		Motor Rated Switch	4	EA	\$80	\$50	\$130	\$520	
32		Three Way Switch	8	EA	\$80	\$50	\$130	\$1,040	
33		Emergency Light Fixture	4	EA	\$350	\$150	\$500	\$2,000	
34		Quadraplex Receptacle	8	EA	\$150	\$100	\$250	\$2,000	
35		Duplex Receptacle Weather Proof	1	EA	\$150	\$100	\$250	\$250	
<b>BLDG A &amp; B - Typ Restroom Power Plan</b>									
36		Above Counter Receptacle	2	EA	\$150	\$100	\$250	\$500	
37		Disconnect Switch Weather Proof	2	EA	\$200	\$100	\$300	\$600	
38		Allowances and Conduits	9000	SF	\$1	\$1	\$2	\$18,000	
<b>E2 Electrical Plan</b>									
<b>Building C - Electrical Plan</b>									
39		Quadraplex Receptacle	24	EA	\$150	\$100	\$250	\$6,000	
40		Emergency Light Fixture	12	EA	\$350	\$150	\$500	\$6,000	
41		Three-way Switch	24	EA	\$80	\$50	\$130	\$3,120	
42		Motor Rated Switch	12	EA	\$80	\$50	\$130	\$1,560	
43		Leviton ODS10 Infrared Wall Switch W/ Manual On/Auto Off	12	EA	\$80	\$50	\$130	\$1,560	

PROJECT ID: Henson Rockland Key

SCOPE: Electrical



## CLIENT'S INFORMATION:

CONTACT:

E-MAIL ADDRESS:

PHONE NUMBER:

Date:

ITEM #	DWG. #	DESCRIPTION	QUANTITY	UNIT	MATERIAL	LABOR	UNIT COST (Labor + Material)	TOTAL COST	TRADE COST
44		Wall Mounted Vanity Fixture (A) Manufacturer: Lithonia Part Number: FMVCCLS 24IN MVOLT 40K 90CRI BN M6	12	EA	\$300	\$150	\$450	\$5,400	
45		Ceiling or Wall Mounted Self Contained Emergency Exit Sign W/ Directional Arrows	24	EA	\$300	\$150	\$450	\$10,800	
46		Duplex Receptacle Weather Proof	1	EA	\$150	\$100	\$250	\$250	
47		Warehouse Fixture W/ OC 50% DIM (B1) Manufacturer: Lithonia Part Number: UFIT L48 8000LM HEF MVOLT GZ10 40K 80CRI LAHOSZU	24	EA	\$300	\$150	\$450	\$10,800	
48		Warehouse Fixture W/ OC 50% DIM (B2) Manufacturer: Lithonia Part Number: UFIT L48 10000LM HEF MVOLT EZ1 40K 80CRI WH LAHOSZU	48	EA	\$300	\$150	\$450	\$21,600	
<b>Building C - Typ restroom Power Plan</b>									
49		Above Counter Receptacle	2	EA	\$150	\$100	\$250	\$500	
50		Disconnect Switch Weather Proof	2	EA	\$200	\$100	\$300	\$600	
51		Allowances and Conduits	13000	SF	\$1	\$1	\$2	\$26,000	
<b>E3 Electrical Plan</b>									
<b>Building A &amp; Building B Power Riser</b>									
52		Grounding Provide (2) Stainless Steel 5/8" Min 10' Sectional Ground Rods W/ Bentonite #1937-R Grade.	1	EA	\$200	\$100	\$300	\$300	
53		Main Lug Terminal Box 1200A 208T/120V 3PH IN 3PH OUT W Breakers	1	EA	\$300	\$100	\$400	\$400	
54		Main Lug Terminal Box 1200A	1	EA	\$300	\$100	\$400	\$400	
55		Panel HA 200A 208/120V	1	EA	\$2,000	\$800	\$2,800	\$2,800	
56		Panel A4 200A 208/120V	1	EA	\$2,000	\$800	\$2,800	\$2,800	
57		Panel A3 200A 208/120V	1	EA	\$2,000	\$800	\$2,800	\$2,800	
58		Panel A1 200A 208/120V	1	EA	\$2,000	\$800	\$2,800	\$2,800	
59		Panel A2 200A 208/120V	1	EA	\$2,000	\$800	\$2,800	\$2,800	
60		Panel HB 200A 208/120V	1	EA	\$2,000	\$800	\$2,800	\$2,800	
61		Panel B4 200A 208/120V	1	EA	\$2,000	\$800	\$2,800	\$2,800	
62		Surge Suppression Device	1	EA	\$300	\$100	\$400	\$400	
63		Panel B2 200A 208/120V	1	EA	\$2,000	\$800	\$2,800	\$2,800	
64		Panel B1 200A 208/120V	1	EA	\$2,000	\$800	\$2,800	\$2,800	
65		Panel B3 200A 208/120V	1	EA	\$2,000	\$800	\$2,800	\$2,800	
66		Surge Suppression Device	1	EA	\$300	\$100	\$400	\$400	
67		Tel/Cat Cabinet	1	EA	\$350	\$150	\$500	\$500	
68		Meter 125 A/3P	5	EA	\$1,000	\$500	\$1,500	\$7,500	
69		Meter 125 A/3P	5	EA	\$1,000	\$500	\$1,500	\$7,500	
<b>E4 Electrical Plan</b>									
<b>Building C Power Riser</b>									
70		Main Service 1 Disconnect 1200A/3P MCB 208Y/120V 3PH IN, 3PH OUT W/ Breakers	1	EA	\$200	\$100	\$300	\$300	
71		Main Service 2 Disconnect 1200A/3P MCB 208Y/120V 3PH IN, 3PH OUT	1	EA	\$200	\$100	\$300	\$300	
72		Panel HC 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
73		Panel C6 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
74		Panel C5 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
75		Panel C4 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
76		Panel C3 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
77		Panel C2 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
78		Panel C1 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
79		Panel C12 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
80		Panel C11 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
81		Panel C10 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
82		Panel C9 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
83		Panel C8 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
84		Panel C7 200A	1	EA	\$2,000	\$800	\$2,800	\$2,800	
85		Tel/CATV Cabinet	1	EA	\$450	\$150	\$600	\$600	
86		Meter 125A/3P	13	EA	\$1,000	\$500	\$1,500	\$19,500	
87		Surge Suppression Device	1	EA	\$300	\$100	\$400	\$400	
88		Grounding Provide (2) Stainless Steel 5/8" Min 10' Sectional Ground Rods W/ Bentonite #1937-R Grade.	2	EA	\$200	\$100	\$300	\$600	
<b>Subtotal (Electrical)</b>									<b>\$329,390</b>

PROJECT ID: Henson Rockland Key

SCOPE: Electrical



**CLIENT'S INFORMATION:**

CONTACT:

E-MAIL ADDRESS:

PHONE NUMBER:

Date:

ITEM #	DWG. #	DESCRIPTION	QUANTITY	UNIT	MATERIAL	LABOR	UNIT COST <small>(Labor + Material)</small>	TOTAL COST	TRADE COST
SUBTOTAL									\$329,390.25
OVERHEAD			15%					\$49,408.54	
INSURANCE			3%					\$9,881.71	
CONTINGENCY			5%					\$16,469.51	
<b>TOTAL BASE BID</b>									<b>\$405,150.01</b>

**Note:**